

S.E.C.Railway

No.W/A/T/QTN/2006-07/Leaky Roof Treatment/66 By Regd.Post with A/D
Bilaspur,dt.17.08.2006

From: The president of India,
Acting through the
Divl.Engineer (Settl.),
S.E.C.Railway/Bilaspur.

To: M/s. Agrawal Agencies,
10, Stadium Complex,
Link Road , Bilaspur (C.G.)

Dear Sir,

Sub: Water proofing treatment on leaky roof to protect leakage in quarters in
Bilaspur Railway Settlement.

x.x.x


Your quotation for the above work has been accepted by the Railway Administration,
S.E.C. Railway, Bilaspur with the rates as shown in the schedule attached and the
conditions as noted below:

CONDITIONS

1. All the works are to be completed with in 30 (Thirteen) days from issue of acceptance letter.
2. The rates are inclusive of all charges towards the works and all other taxes leviable by the state/central Governments.
3. All the terms and conditions as embodied in the S.E.Railway, SOR-1992 Vol-I & SOR-2001 Vol-II will form part and parcel of the agreement.
4. Contract value of this work is fixed for ~~₹. 10,00,000/-~~ (Ten Lakhs only).
5. Earnest money submitted vide MR No.012483 dt.30.06.05 for ~~₹. 10,00,000/-~~ issued by Divl. Cashier(Cash)/SECR/Bilaspur will be kept as in security deposit and rest of amount will be deducted from bills.
6. The security deposit of the contractor will be refunded only after successful completion of all the work and settlement of all dues, less debit, if any according to the condition of the agreement.

You are therefore, requested to attend this office within 7 days from the date of receipt of this letter, for signing the agreement of this work failing which, action will be taken as per rules. Please note that the agreement is kept ready for your signature.

Yours faithfully,


DEN(Settl.)Bilaspur
For & on behalf of president of India
S.E.C.Railway/Bilaspur

Copy to : Sr.DFM/BSP, ADEN(Settlement-I), S.E.(Works)/West/BSP, Bill Section
Sr.DEN (Co-Ord.)/BSP office.

DEN(Settlement),
S.E.C.Railway/Bilaspur

Annexure-I

| Sl. No | Description of work | Qty. | Rate | Amount (in Rs) |
|--------|--|------|------|----------------|
| 1 | Cleaning of existing roof surface with iron brush and water. Cracks are to be filled by "Diamond Shield" of CHITRA INSULTEC PVT. LTD or equivalent chemical suitably diluted. After curing 3 to 4 hours applying two coats "Sealer Coat" of CHITRA INSULTEC PVT. LTD or equivalent materials by diluting 15% to 20% by giving 3 to 4 hours gap between each coat, including all materials, taxes and labour, ascent, descent, lead etc in all respect of contractor. | Sqm. | | |
| | Total | | | |

Note:-


Roof treatment by chemicals on existing leaky/seepage roofs with the method as below:

1. Scarifying the existing slab by wire brush and making thoroughly clear suitable to receive chemical treatment.
2. Opening of cracks.
3. Filling of cracks by "Diamond Sheild" of CHITRA INSULTEC PVT. LTD or equivalent chemical suitably diluted.
4. After curing 3 to 4 hours, applying two coats of "Sealer Coat" of CHITRA INSULTEC PVT. LTD.

Special Condition:

- 1 The work should be completed within 30 days from the date of issue of the acceptance letter
- 2 S.E.Railway General Condition of Contract and standard specification Vol.II-2001 will be applicable in this contract
- 3 It is the sole responsibility of the contractor for safety of his labour, tools and plants, materials while executing the work.
- 4 Leakage test should be done by ponding method and sample area should be 20 % of the area per 1000 Sqm or part there of. After satisfactory result payment will be made.

Signature of tenderer(s)


Divl.Railway Manager(Engg.)
S.E.C.Rly., Bilaspur
For and on behalf of president of India